· ·

(Q)

Report No. VSE/ASD/0136-89/04RD

### AD-A210 721

FINAL TECHNICAL REPORT FOR 18,000 BIUH COMPACT VERTICAL AND HORIZONTAL TOTAL ENVIRONMENTAL CONTROL SYSTEM (TECS), 0500.0136

VSE Corporation 2550 Huntington Avenue Alexandria, VA 22303-1499



31 January 1989

Final Report for Period 29 July 1988 through 31 January 1989

Approved for public release; distribution is unlimited.

#### Prepared for:

US Army Belvoir Research, Development and Engineering Center Environmental Control and Systems Support Division (STRBE-FED) Fort Belvoir, VA 22060-5606

The views, opinions, and/or findings contained in this report are those of the author(s) and should not be construed as an official Department of the Army position, policy, or decision, unless so designated by other documentation.

35

129

SECURITY CLASSIFICATION OF THIS PAGE					
	REPORT DOCU	MENTATION	PAGE		
18 REPORT SECURITY CLASSIFICATION		16. RESTRICTIVE	MARKINGS		<del> </del>
UNCLASSIFIED	·	<u> </u>			
2a. SECURITY CLASSIFICATION AUTHORITY		3 DISTRIBUTION/AVAILABILITY OF REPORT APPROVED FOR PUBLIC RELEASE:			
26. DECLASSIFICATION / DOWNGRADING SCHED	ULE	7	rok poblic rion unlimin		
		DISTRIBUTE.			
4. PERFORMING ORGANIZATION REPORT NUMB	ER(S)	5. MONITORING	ORGANIZATION R	EPORT NUMBER	R(S)
VSE/ASD/0136-89/04RD					
64. NAME OF PERFORMING ORGANIZATION	6b. OFFICE SYMBOL	7a. NAME OF MO	NITORING ORGA	NIZATION	
	(If applicable)		TAL CONTROL		SUPPORT
		1	DIVISION (S	TRBE-FED)	
6c. ADDRESS (Gty, State, and ZIP Code)		7b. ADDRESS (Cit)	•		
2550 HUNTINGTON AVENUE		I.	BELVOIR RE		VELOPMENT
ALEXANDRIA, VA 22303-1499		ŧ	NEERING CENT		
84. NAME OF FUNDING/SPONSORING	8b. OFFICE SYMBOL	9. PROCUREMENT	OIR, VA 220		HIMRER
ORGANIZATION	(If applicable)	3. PROCUREMENT	M31KUMENT ID	ENTIFICATION N	OIAIGEK
US Army, Belvoir	STRBE-FED	DAAK70-8	36-D-0023		
8c. ADDRESS (City, State, and ZIP Code)		10. SOURCE OF F	UNDING NUMBER	rs .	
U S ARMY BELVOIR RESEARCH,	DEVELOPMENT	PROGRAM	PROJECT	TASK	WORK UNIT
AND ENGINEERING CENTER		ELEMENT NO.	NO.	NO.	ACCESSION NO
FT. BELVOIR, VA 22060-5606		J	0500	0136	
11 TITLE (Include Security Classification) FINAL TECHNICAL REPORT FOR 1	8.000 BTUH COMPA	CT VERTICAL A	ND HORIZONT	AL TOTAL	
ENVIRONMENTAL CONTROL SYSTEM					
12. PERSONAL AUTHOR(S)		· · · · · · · · · · · · · · · · · · ·			······································
BAKER, MA	ARK S.				
13a. TYPE OF REPORT 13b. TIME (	OVERED	14. DATE OF REPO	RT (Year, Month,	Day) 15. PAG	
FINAL FROM 88	1/7/29 <b>10</b> 89/1/31	88/1/3	31		19
16. SUPPLEMENTARY NOTATION	1/2/000 2/0000				
DESTROY THIS REPORT WHEN NO	LONGER NEEDED.	DO NOT RETURN	TO THE ORI	GINATOR.	
17 COSATI CODES	18. SUBJECT TERMS (	Continue on reverse	if necessary and	identify by ble	ock number)
FIELD GROUP SUB-GROUP	18K BTUH HORI	ZONTAL TECS,	18K BTUH VE	RTICAL TEC	S PROTOTYPE
13 01	FABRICATION,	CONTROLS TEST	CING, RUN-IN	TESTING,	MOTOR CON-
	TROLLER, COMM	ERCIAL COMPRE	SSOR, MILIT	ARY COMPRE	SSOR, HEATER
19. ABSTRACT (Continue on reverse if necessary	and identify by block i	number)		М	ODIFICATION.
			,		
VSE PROVIDED PROTOTYPE MANUF					
SUPPORT DEVELOPMENT OF TWO 1					
CONDITIONERS. THESE FOUR AI					
THAT COMPARATIVE DATA COULD TESTING WERE PERFORMED ON TH					
WITHOUT A MOTOR CONTROLLER A				AIR CONDI	
WERE ALSO USED TO EVALUATE U				AIR CONDI	TIONERS
		COM RECORD.	,		
		,:			
		ر		•	
		•			
20 DISTRIBUTION/AVAILABILITY OF ABSTRACT		21. ABSTRACT SEC	TIBITY OF ACCIEN	ATION	
☐ UNCLASSIFIED/UNLIMITED  ☐ SAME AS		· · · · . · . · . · . · . ·	SSIFIED	,	
223 NAME OF RESPONSIBLE INDIVIDUAL	COUNT COSEKS	226. TELEPHONE (A		) 22c. OFFICE	SYMBOL
Mr. THOMAS SGROI		(703) 66		STRBE-	

DD FORM 1473, 84 MAR

83 APR edition may be used until exhausted. All other editions are obsolete

SECURITY CLASSIFICATION OF THIS PAGE

#### SUMMARY

Task Order 0136 required that VSE provide general technical services to the Environmental Control and Systems Support Division of the Belvoir Research, Development and Engineering Center, Fort Belvoir, Virginia in support of the Government's 18,000 (18K) BIUH Total Environmental Control System (TECS) development effort. A total of four (4) 18K BIUH TECS air conditioners were modified and reconfigured by incorporating motor controllers into two (2) 18K BIUH standard vertical air conditioners and two (2) standard horizontal air conditioners. The four units are referred to as "baseline" units and were used to acquire comparative test data. These baseline units were first tested by the Government in their standard configuration. The units were then provided as Government Furnished Equipment (GFE) to VSE for incorporation of motor controllers and associated components to convert them into TECS units. The Government is currently testing the baseline units in order to compare test data with previous test data resulting from the urmodified baseline tests.

The baseline units were also used to evaluate the suitability of commercial compressors for a possible replacement of the military compressor in the 18K BIUH TECS air conditioners. Commercial compressors were not included in the final TECS unit design due to unfavorable test results.

Accesion	For			
NTIS C		<u> </u>	 	
Unannoi Justifica				
By Distribu	tion /			
AV	adability	Code	s	
1	A and as a superior of the sup			

#### PREFACE

This Final Technical Report was prepared under Contract No. DAAK70-86-D-0023, Task Order 0136, for the Belvoir Research, Development and Engineering Center (Belvoir), Fort Belvoir, Virginia. Mr. Thomas Sgroi served as the Belvoir Contracting Officer's Representative, telephone no. (703) 664-6031.

This report represents the final effort for support of the 18K BTUH TECS baseline air conditioners to be provided under Task Order 0136. The required effort in the Task Order statement of work is quoted below:

"The purpose of this Task Order is to provide engineering evaluation, prototype manufacturing, documentation and testing services in support of incorporating motor controllers into two (2) 18,000 BTUH compact Vertical and two (2) Horizontal Military Standard Air Conditioners which are being tested by the Government to establish baseline data for comparative purposes. This modification will result in air conditioners with "soft start" electronics installed internally. "Soft-start" is defined as operating the air conditioner such that start-up current does not exceed full load steady-state current required for the air-conditioner (with controls). These modified air conditioners shall be referred to as Total Environmental Control Systems (TECS). The contractor shall utilize knowledge gained during the performance of Contract No. DAAK70-86-D-0023, Task Order No. 0074 to accomplish this task."

### TABLE OF CONTENTS

Paragraph	<u>Title</u>			
	SUMMARY PREFACE	ii iii		
1,0	INTRODUCTION	1		
2.0 2.1 2.2 2.3 2.4	DISCUSSION  General  Commercial Compressor (Copeland Corporation)  Controls/Run-in Testing  Engineering Evaluations and Design Modifications	1		
3.0	CONCLUSION	3		
4.0	RECOMMENDATION	4		

#### 1.0 INTRODUCTION

Task Order 0136 required VSE Corporation to provide technical support for the Government's 18,000 (18K) BTUH Total Environmental Control System (TECS) Program. The primary purpose of this task was to provide shop fabrication services to modify and reconfigure four (4) 18K BTUH TECS air conditioners by incorporating motor controllers into two (2) 18K BTUH standard vertical air conditioners and two (2) standard horizontal air conditioners. TECS unit fabrication was performed in accordance with the Government Furnished Data (GFD) Level 1 vertical and horizontal TECS drawing packages prepared under Task Order 0074, Contract No. DAAK70-86-D-0023. The four TECS units which were modified and reconfigured were designated as "baseline" units. four prototype units were to be used to acquire comparative data between the new TECS design and the standard 18K BIUH Army air conditioner. The four baseline units augmented the eight (8) "reliability" units fabricated under Task 0074. Basically the reliability units are intended for long duration reliability testing while all other short term testing such as capacity, EMI, vibration, rain, high/low temperature operation, coil frost, noise, etc. will be performed on the baseline units. The baseline units were also used to evaluate use of commercial compressors in the TECS unit.

#### 2.0 DISCUSSION

- 2.1 <u>General</u>. VSE provided prototype manufacturing, testing, documentation and engineering evaluation (as required) services in support of motor controller incorporation into four 18K BTUH air conditioners.
- Four (4) 18K BIUH TECS air conditioners were fabricated and delivered to Belvoir. Controls and run-in testing were performed on three of the air conditioners. Testing was not performed on the fourth unit due to nonavailability of a motor controller.

No design modifications were incorporated into the GFD Level 1 drawing package as a result of this task order. However, the wiring of the electrical resistance heaters were changed on the horizontal unit which will be reflected in the Level 3 TDP at some later date.

A commercial compressor was substituted for the original military design compressor in the baseline units to determine suitability. The commercial compressor evaluation effort was abandoned following failure to meet cooling capacity requirement in accordance with the air conditioner specification.

2.2 <u>Commercial Compressor (Copeland Corporation)</u>. The existing compressors used in the standard 18K BIUH air conditioners are source controlled items. The qualified sources of supply for the horizontal unit include Carrier Corporation, Welco Industries and Keco Industries, and for the vertical include Carrier Corporation and Welco Industries. These compressors are actually commercial units which are upgraded to withstand the military environment. The upgrades consist of cutting open the hermetically sealed compressors and upgrading the vibration mounts and/or rewinding or replacing the electric motor. This modification or militarization disrupts the mass production process and is therefore extremely costly to the Government. This

effort was intended to reevaluate current commercial compressors available, select the best candidate compressor, and to determine if it is suitable for use in the TECS air conditioners.

The Government tested the baseline air conditioners with the installed military compressors prior to the VSE TECS modification. Government testing included the following:

- o Performance
- o Cooling capacity and airflow
- no High temperature operation
  - o Low temperature operation
  - o Weight

The Government then replaced the military compressors with commercial compressors and started similar testing. The candidate commercial compressors were selected by VSE from GFD in the form of a market investigation. The VSE selection was based primarily on size and cooling capacity rating. VSE's calculations indicated that the cooling capacity of the commercial compressor selected (Copeland Corporation Model CRD1-0200-TF5, nominal rating - 24,000 BIUH) was marginal for the air conditioner. However, the size constraints of the air conditioner condenser compartment limited the size of the candidate compressor. The size of the next higher rated compressor was too large for the air conditioner. Government testing with the commercial compressors was to include the following:

- o Performance\*
- o Cooling capacity and airflow\*
- o Heating capacity
- o EMI emissions
- o Noise level
- o High temperature operation
- o Low temperature operation
- o Weight

\*Only tests were actually performed.

The air conditioner cooling capacity with the commercial compressor was below the minimum required capacity specified in MIL-A-52767C. Therefore, the Government decided not to include the commercial compressors in the final TECS unit design. The Government then provided the baseline air conditioners to VSE as Government Furnished Equipment (GFE) for TECS modification. VSE replaced the commercial compressors with the original military compressors as a part of the modifications necessary to reconfigure these units to TECS units.

- 2.3 <u>Controls/Run-in Testing</u>. Following reconfiguration, a controls test was performed on three of the four baseline air conditioners. In addition to the controls test, an eight (8) hour run-in test was performed on three of the four air conditioners. During run-in, a portion of the condenser discharge air was ducted to the condenser intake such that 120°F inlet air temperature was maintained. The following data was measured and recorded each hour during the run-in test:
  - o Condenser inlet air temperature

- o Evaporator inlet air temperature
- o Phase A current
- o Phase B current
- o Phase C current
- o Sight glass condition

Data sheets for the controls test/run-in test are provided in Appendix A. Formal testing was performed on TECS unit S/N's B009, 831747 and 831791. Testing was not performed on TECS unit S/N B007 since no motor controller was available. VSE was expecting delivery of a reworked motor controller from Southern Industrial Controls (Southcon) which would subsequently be installed in TECS unit S/N B007. However, due to the urgency of the TECS design verification testing program at Belvoir, the final baseline unit was delivered without a motor controller per Belvoir instructions. Prior to delivery of air conditioner S/N B007, VSE did determine TECS unit S/N B007 was functional using a motor controller from another TECS unit.

2.4 Engineering Evaluations and Design Modifications. No design modifications were made to the Level 1 TDP as a result of this task order. The location of the electrical resistance heater wiring was reconsidered under this task. Originally the heater banks were connected on the input of the motor controller. This configuration reduced the load on the motor controller during heating however, it necessitated an unbalanced load on the supply power source due to heater element design compromises required for the 208V, 3 phase and 230V, single phase input power conditions.

Connecting the heaters to the output of the motor controller adds a resistive load on the motor controller and provides for balanced loading on the supply power source. Keco Industries indicated that the increased resistive load on their motor controller would present no problems. Southcon on the other hand indicated concern about cooling of their power transistors under a 10 amp resistive load. Southcon's response was basically "try it and see" (See Appendix B for summaries of significant telephone conversations). Rewiring the heaters to the output of the motor controllers also enables the use of the original heater and heater bracket design for the 18K horizontal TECS unit. Belvoir decided to make this change to insure a balanced load condition on the supply power source. This change will be incorporated into the Level 3 TDP being developed for Belvoir by Radian, Inc. of Alexandria, VA.

#### 3.0 CONCLUSION

Two (2) 18K horizontal TECS and two (2) 18K vertical TECS air conditioners were fabricated in accordance with GFD Level 1 drawings, subjected to controls and run-in testing (three units only), and delivered to Belvoir. VSE was not required to perform any design modifications to the TECS drawing packages as a result of Task 0136. Belvoir required modifications to the TECS heater configuration consisting of heater rewiring for the horizontal unit, and reversion to the previous heater element and heater bracket design used in the original 18K horizontal TECS TDP. This change will be incorporated into the TECS drawing package by another Government contractor responsible for Level 3 TDP development.

Commercial compressors were installed and tested by the Government in the 18K horizontal and vertical air conditioners prior to VSE conversion of the air conditioners into TECS units. Insufficient cooling capacity necessitated the Government to require VSE to replace the commercial compressor with the military design compressors during TECS prototype fabrication.

#### 4.0 RECOMMENDATION

The military design compressors should be used in the 18K BTUH TECS air conditioners. The reduction in cooling capacity with the commercial compressor should not be acceptable. Though vibration testing was not performed with the commercial compressor, it is anticipated that failures would result due to the relatively light internal vibration mounts provided with a commercial unit.

The Belvoir test program should be completed to identify any undesirable operation of the 18K BTUH TECS air conditioners. Any modifications required should be performed on prototype TECS units and tested as quickly as possible to insure inclusion in the TDP for the upcoming TROSCOM, FY89 18K BTUH air conditioner procurement.

### APPENDIX A

TEST DATA SHEETS - CONTROLS/RUN-IN TESTING

## OC TESTING DATA SHEET FOR OPERATIONAL VERIFICATION OF TECS 18KBTU HORIZONTAL UNITS

DATE OF TEST 9-38-88

QC INSPECTOR R. ROUZE

#### A) FUNCTION TEST

QC INT.

1) WITH UNIT OFF AND POWER APPLIED TO J4
ROTATE MODE SWITCH TO THE VENT POSITION. AFTER
APPROX. 6-7 SECONDS THE BLOWER SHALL START TO RUN.

R

- 2) RETURN MODE SWITCH TO THE RESET POSITION AND WAIT APPROX. 6-7 SECONDS FOR THE UNIT TO RESET.
- 3) WITH THE TEMPERATURE SWITCH IN THE FULL CCW POSITION, ROTATE THE MODE SWITCH TO THE HEAT FOSITION. AFTER APPROX. 6-7 SECONDS THE BLOWER SHALL START TO RUN.USING A TEMPERATURE PROBE VERIFY THE TEMPERATURE OUTPUT. TEMP 72 F

R

4) ROTATE THE TEMP SWITCH TO THE FULL CW POSITION. AN AUDIBLE CLICK SHOULD BE HEARD AND THE HEATERS SHALL COME ON. USING A TEMPERATURE PROBE VERIFY THE TEMPERATURE OUTPUT. TEMP 86 FIF THE TEMP IN STEP 4 JS HIGHER THAN IN STEP 3 THEN THE THERMOSTAT IS FUNCTIONING PROPERLY.



- 5) SAME AS STEP 2.
- 6) WITH THE TEMPERATURE SWITCH IN THE FULL CW POSITION, ROTATE THE MODE SWITCH TO THE COOL POSITION. AFTER APPROX. 6-7 SECONDS THE BLOWER SHALL COME ON. USING A TEMPERATURE PROBE VERIFY THE TEMPERATURE OUTPUT. TEMP

R

7) ROTATE THE TEMP SWITCH TO THE FULL CCW POSITION. THE BLOWER SHALL SHUT OFF FOR APPROX. 6-7 SECONDS, AFTER WHICH THE COMPRESSOR SHALL COME ON. USING A TEMPERATURE PROBE VERIFY THE TEMPERATURE OUTPUT. TEMP S9 F IF THE TEMPIN STEP 7 IS LOWER THAN IN STEP 6 THEN THE THERMOSTAT IS FUNCTIONING PROPERLY.

R

#### B) ENDURANCE TEST

1) USING SOME TYPE OF DUCTING DEVICE DEFLECT THE HOT AIR OUTPUT INTO THE AIR INTAKE. USING A TEMP PROBE MONITOR THE TEMPERATURE OF THE INTAKE AIR SO THAT 120F IS MAINTAINED. RUN THE UNIT IN THE HIGH COOL MODE FOR A MINIMUM OF 8 HRS. UNIT SHALL NOT CUT OUT DURING THIS TIME.

TIME OF TEST START 9:00 AM

TIME OF TEST STOP 3:25 pm

DATE 9-28-88

COMMENTS/REMARKS:				<del> </del>
		····		
	<del></del>		·	

	TIME	T1	T2	SIGHT GLASS	(	CURRENT	
	10:00	119	59	CONDITION CLEAR / LIME	RED 12.7	WHITE 12.5	BLACK 12.7
	11:00	199	61	CLEAR / LIME	12.9	12.8	13.01
-	12:00	125	63	CLEAR LIME	12.9	12.7	13.0
	1:00	127	64	CLEAR / LIME	13,0	12.9	13.2
	2.50	129	67	Clear/Lime	13.2	13.1	13.8
THET 1:301M	3.00		Shu	down	14.7	14.6	15.1
7-29-88	2:10	119	51	CLEAR LIME	11.3	11.2	11.5
M	3:20	120	51	CLEAR LUME	11.3	11.1	11.5
	4:00	119	50	CLEAR LIME	11.3	11.2	11.5
	5:40	1189	51	CLEAN/LINE	11.2	11-1	11.5
,	5:45	SI	tut	Down			•

## OC TESTING DATA SHEET FOR OPERATIONAL VERIFICATION OF TECS 18KBTU VERTICAL UNITS

s/n of unit under test B009	
DATE OF TEST9-1-88	
QC INSPECTOR R. ROVER	
A) FUNCTION TEST	QC INT.
1) WITH UNIT OFF AND POWER APPLIED TO J4 ROTATE MODE SWITCH TO THE VENT POSITION. AFTER APPROX. 6-7 SECONDS THE BLOWER SHALL START TO RUN.	R
2) RETURN MODE SWITCH TO THE RESET POSITION AND WAIT APPROX. 6-7 SECONDS FOR THE UNIT TO RESET.	R
3) WITH THE TEMPERATURE SWITCH IN THE FULL CCW POSITION, ROTATE THE MODE SWITCH TO THE HEAT POSITION. AFTER APPROX. 6-7 SECONDS THE BLOWER SHALL START TO RUN.USING A TEMPERATURE PROBE VERIFY THE TEMPERATURE OUTPUT. TEMP 76 F	k
4) ROTATE THE TEMP SWITCH TO THE FULL CW POSITION. AN AUDIBLE CLICK SHOULD BE HEARD AND THE HEATERS SHALL COME ON.USING A TEMPERATURE PROBE VERIFY THE TEMPERATURE OUTPUT. TEMP SIF THE TEMP IN STEP 4 IS HIGHER THAN IN STEP 3 THEN THE THERMOSTAT IS FUNCTIONING PROPERLY.	R
5) SAME AS STEP 2.	

6) WITH THE TEMPERATURE SWITCH IN THE FULL CW POSITION, ROTATE THE MODE SWITCH TO THE COOL POSITION. AFTER APPROX. 6-7 SECONDS THE BLOWER SHALL COME ON. USING A TEMPERATURE PROBE VERIFY THE TEMPERATURE OUTPUT. TEMP 82 F

R

#### B) ENDURANCE TEST

1) USING SOME TYPE OF DUCTING DEVICE DEFLECT THE HOT AIR OUTPUT INTO THE AIR INTAKE. USING A TEMP PROBE MONITOR THE TEMPERATURE OF THE INTAKE AIR SO THAT 120F IS MAINTAINED. RUN THE UNIT IN THE HIGH COOL MODE FOR A MINIMUM OF 8 HRS. UNIT SHALL NOT CUT OUT DURING THIS TIME.

TIME OF TEST START 9:45 AM retest 1:30 PM
TIME OF TEST STOP 5:45

DATE 9-1-88

9-2-88

COMMENTS/REMARKS: 2 1cmp. Increased Steadily throughout test. Upon investigation by PE value \_\_\_ was Sticky". Value was cleaned and unit was run for approx. 3 HRS. CONDENDER INPUT Temp 121°F, output air 52°. Upon removed of ducting by QC output air temp rose to 61°F, held for 30 sec and dryped to 56°F where it stabilized. Unit was start off. After reset unit outputain temp decreased to mid 40'3. Value still appears to be "Sticky" SIGHT GLASS TIME T1 T2 CURRENT CONDITION RED WHITE BLACK SOLDER CHIP @ STAFT 9:45 122 670 LIME /CLEAR 8.4 9.2 8.7 68 123 8.6 8.8 10:45 9.2 LIME / CLEAR CLEAR 11:45 7.9 120 UME 8.7 8.Z 8.0 8.3 12:45 72 ZIJUME! CLEAR 121 88 7.9 8.4 1:45 122 LIME ( CLEAR 8.8 73 121 UNE / CLEAR 7.9 2:45 8.Z 8.5 122 LIME / CLEAR 7.8 3:45 8.1 8.5 8.0 4:45 120 7.5 8.4 LIME CLEAR 7.4 LIME I-CLEAR 119 5:45

## OC TESTING DATA SHEET FOR OPERATIONAL VERIFICATION OF TECS 18KBTU HORIZONTAL UNITS

S/N OF UNIT UNDER TEST 831747

CDATE OF TEST 8-30-88

OC INSPECTOR R. ROVZER

#### A) FUNCTION TEST

QC INT.

1) WITH UNIT OFF AND POWER APPLIED TO J4
ROTATE MODE SWITCH TO THE VENT POSITION. AFTER
APPROX. 6-7 SECONDS THE BLOWER SHALL START TO RUN.

R

2) RETURN MODE SWITCH TO THE RESET POSITION AND WAIT APPROX. 6-7 SECONDS FOR THE UNIT TO RESET.

R

R

4) ROTATE THE TEMP SWITCH TO THE FULL CW POSITION. AN AUDIBLE CLICK SHOULD BE HEARD AND THE HEATERS SHALL COME ON.USING A TEMPERATURE PROBE VERIFY THE TEMPERATURE OUTPUT. TEMP 75 FIF THE TEMP IN STEP 4 IS HIGHER THAN IN STEP 3 THEN THE THERMOSTAT IS FUNCTIONING PROPERLY.

R

- 5) SAME AS STEP 2.

D

7) ROTATE THE TEMP SWITCH TO THE FULL CCW POSITION. THE BLOWER SHALL SHUT OFF FOR APPROX. 6-7 SECONDS, AFTER WHICH THE COMPRESSOR SHALL COME ON. USING A TEMPERATURE PROBE VERIFY THE TEMPERATURE OUTPUT. TEMP 56 F IF THE TEMPIN STEP 7 IS LOWER THAN IN STEP 6 THEN THE THERMOSTAT IS FUNCTIONING PROPERLY.

# WASHINGTON REGION QUALITY CONTROL SHOP REQUEST FOR INSPECTION

FORM

DATE: Aug 29, 1988 TIME: 12:45 JOB No.: 0500-0136	
UNIS NO.: 10451 HORIZONTAL 831747	
TEM DESCRIPTION: The check out Su. 16. 74	7
TYPE OF INSPECTION REQUIRED:  IN-PROCESS *** WELDING	
OTHER	
INSPECTION REQUESTED BY: Life M Agl.	
SPECIAL INSTRUCTIONS:	_
	_
	_

OC FORM XXXX

# APPENDIX B SIGNIFICANT TELEPHONE CONVERSATIONS

### TELECON

JOB NO.: 0500.0136 TITLE: TECS - 18 Pateline
DATE: 18/18/88 TIME: 10:30 /1 M
CALLER: Bob Slyn G.
CALLED: PERSON: John Dupps
COMPANY: KECO Industries, Inc
ADDRESS: Florence, KY
PHONE: (606) 525-2102
SUBJECT: Motor Controller Output
( sloku Duppe returned my exil to
him yesterday)
SUMMARY OF CALL: When I asked if the Vrio Mic
controls output voltage when input voltage
is varied, his answer was yes, purbably
within 506, This is done by sensing the
De buse voltage and varying the pulse
width fulce with decreases at higher
input voltager and increases at lower input
Voltages to greed a relatively constained and relatively
output voltage. Where Southern receivly
expressed some concern over running a
resistive load on the MC output, Kero
sees ne problem. Lahuis working on
increasing output correct to operate units
ost 120°F/120°F conditione. I remaided him DISTRIBUTION: SEMULTANEOUS low voltage requirement.
DISTRIBUTION: SEMUITANZONS 10W VOLTAge 1-Equirement.
Ton- Sgraif Chrie Bolton
Lincoln Hay
0/36 and 0074 files

### TELECON

JUB NU.: DSUO.0136 TITLE: TECS -18 BASELINE
DATE: 10/17/88 TIME: 2-38 PM  CALLER: 130B SHERFY
CALLER: BOB SHERFY
CALLED: PERSON: JIM BRADLEY  COMPANY: SOUTH CON
ADDRESS: CHARLOTTE, NC
PHONE: (7.04) 588-8000
SUBJECT: Motor Controller Output
SUMMARY OF CALL: Tasked Sim if the Gouthicon Mc's
out put voltage is controlled so that it will
not very as the imput voltage changes from
184 VAC to 2-53 VAC. He ryplied yes,
It probably does not get higher than about
2-15 VAC. He was wore vague about low
voltage lowerer, implying that there is also
control vader law voltage conditions but
·
not voing exact wembers. I'm was somewh
concerned about vering more than about 10 augs into
a resistive load. He said give it a try and
see what happene Hic Concern is for cooling or
the power transictors which must operate continuously
with a resistive load. (Output RMS voltage is controll DISTRIBUTION: arying pulse width.
. *
Your SGROT / CHRIS BULTON
LINCOLM HAY.
FINEC 0074 and 0/36.